



(A Govt. of India Enterprise)

O/O SUB DIVISIONAL ENGINEER (CIVIL),
BSNL CIVIL SUB DIVISION, DHANBAD

No. : Quotation/SD-DNB/2018-19/21

Date: : 31.07.2023

NOTICE INVITING QUOTATION

No: **01/NIQ/CSD/DNB/23-24 dated 31.07.2023**

The Sub Divisional Engineer (C), BSNL Civil Sub Division, **Dhanbad**, 3rd floor, **CTO Building, Hirapur, Dhanbad-826001** invites for and on behalf of **Bharat Sanchar Nigam Limited** sealed item rate quotations from approved and eligible contractors of D.O.T / BSNL and contractors registered with other Public Works Organizations like CPWD, Jharkhand state PWD (B&R), DOP, MES and Railways. for the following work:

Sl. No.	Name of work	Estimated Cost (in Rs.)	Time allowed for completion
1.	Necessary civil works in the water filter space in the corridor, 2nd floor, CTO building, Dhanbad. (BA: Dhanbad)	8063.00	07 (Seven) days

Quotation paper can be had on application from the O/o the Sub Divisional Engineer ©, BSNL Civil Sub Division, Dhanbad or can be downloaded from the website www.jharkhand.bsnl.co.in .

Application for issue of quotation shall be received in the above office up to 1400 hrs. **04.08.2023** and quotation paper will be issued on same day up to 1430 hrs. Sealed quotations will be received upto 15.00 Hrs on **05.08.2023** and will be opened on the same day at 1530 Hrs in presence of quotationers or their authorized representative. In case, holiday is declared on the quotation opening day, the quotation will be opened on the next working day. Quotation with any condition including conditional rebates shall be summarily rejected.

TERMS AND CONDITIONS: -

- The agency should quote the rate in figure as well as in words in respect of rate and amount.
- The agency should visit the site before offering quotations and satisfy himself as to the condition prevalent there & no claims what so ever shall be entertained on this ground.
- Quotation should be placed in sealed cover including the name of work as mentioned above.
- Unsealed quotation shall be liable to be rejected.
- Payment will be made after completion of work in all respect.
- Time for completion of work is **07 (Seven) days** from the date of issue of work order to commence the work and to be strictly adhered to.
- The site should be cleaned in all respect after completion of the work.
- In case, any dispute arises, the decision of the Engineer –in-charge shall be final and binding.
- The acceptance of Quotation will rest with the Sub Divisional Engineer (C), BSNL Civil Sub Division, Dhanbad or the higher authority of BSNL Civil wing. The competent authority of BSNL reserves the right to reject any or all quotations without assigning any reason thereof.

- The agency should supply all tools and plants for the work.
- The rate quoted by the agency /bidder shall be inclusive of all taxes (i/c GST), levies, Cess, freight, forwarding, packaging and insurance charges. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
- The rates quoted by the agency shall also be inclusive of 1 % (one percent) worker's well fare Cess on the work done and shall be recovered from running / final bill as applicable on the building and other construction workers welfare Cess Act, 1996 due to introduction of "The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996".
- The rate quoted by the quotationers shall be valid upto one month from date of submission of the bids.

Sd/-
Sub Divisional Engineer (Civil)
BSNL Civil Sub Division
Dhanbad

Copy to: -

1. The GM BA, BSNL Dhanbad.
2. The Superintending Engineer(C), BSNL Civil Circle, Ranchi.
3. The Executive Engineer (Civil) BSNL Civil Division, Jamshedpur.
4. The Sub Divisional Engineer(C), BNSL Civil Sub Division Bokaro/Dumka/Jamshedpur-I/II
5. Notice board/ Spare Copy.
6. Website www.jharkhand.bsnl.co.in

Sd/-
Sub Divisional Engineer (Civil)
BSNL Civil Sub Division
Dhanbad

Schedule of Quantity

Name of work: - Necessary civil works in the water filter space in the corridor, 2nd floor, CTO building, Dhanbad. (BA: Dhanbad)

Time allowed – 07 (Seven) days.

Sl. No.	Description of Item	Quantity	Unit	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a)	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	0.10	cum		
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	4.00	kg		
3	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	1.00	sqm		
4	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	0.85	sqm		
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape,raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.				
a)	With cement mortar 1:4 (1cement: 4 coarse sand)	2.00	sqm		

Sl. No.	Description of Item	Quantity	Unit	Rate	Amount
6	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
a)	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.05	cum		
7	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
a)	Of area 3 sq. metres and below	1.00	each		
8	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
a)	For thickness of tiles 10 mm to 25 mm	1.25	sqm		
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall				
a)	50 mm nominal dia Pipes	0.30	metre		
10	Providing and fixing PTMT stop cock of approved quality and colour.				
a)	15 mm nominal bore, 86 mm long, weighing not less than 88 gms	1.00	each		
11	Providing and fixing PTMT grating of approved quality and colour.				
a)	Circular type				
i)	100 mm nominal dia	1.00	each		
12	Cutting holes up to 30x30 cm in walls including making good the same:				
a)	With common burnt clay F.P.S. (non modular) bricks	1.00	each		

Sl. No.	Description of Item	Quantity	Unit	Rate	Amount
13	Providing and fixing 18 mm thick granite stone slab of size 0.65 m x 0.50 m in the water filter space at 2nd floor of CTO building, Dhanbad, including moulding and rounding of edges, cutting chases of adequate thickness/depth in the adjoining brick wall for supporting the slab with cement mortar, treating the joints with white cement, all complete i/c all T & P, labour involved as per direction of Engineer-in-charge.(Additional steel brackets for support to be provided and paid separately.)	1.00	One job		
14	Cleaning of wall tiles of water filter space in corridor adjacent to the common wash room at 2nd floor, CTO building with acid/tile cleaner using scrubbers to remove dirt/stains , all complete as per direction of the Engineer-in-charge.	1.00	One job		

Sd/-
Sub Divisional Engineer (C)
BSNL Civil Sub Division
Dhanbad

Signature of Contractor/ Agency